



CUSTOM TANK



Case Study 2021

PROBLEM:

Multi-Use, Multi-Leased Industrial Park Exceeding Benchmark of both Zinc & Copper being taken over by the Industrial Park and combining all the individual industrial permits. Industries adding to the levels included a metal recycler shredding facility, multiple steel fabricators, a steel retail storage location and a public truck/vehicle roadway. Site is located in the NW near a major river.

SOLUTION:

After evaluating proposals from three companies to treat the combined stormwater, the choice was to utilize **BiocharPEAT™** in a 350 GPM pump station with a 12' x 22' x 8' tall **Pure Rain™ CUSTOM TANK** built locally. The **Pure Rain™ CUSTOM TANK** includes 25 cubic yards of **BiocharPEAT™** treatment.



FLOW DESIGN:

An existing catch basin had a weir added to it with a pipe on the influent side put into it to gravity feed the water to a new vault. In the vault, two 350 GPM pumps were installed to pump the water to the **Pure Rain™ CUSTOM TANK**. The stormwater then gravity flows through the **Pure Rain™ CUSTOM TANK** and back to the discharge side of the catch basin with the weir and leaves the site to the river.

Stormwater **BIOCHAR**.COM

STORMWATER TREATMENT

TEN 10 YEARS STRONG
stormwater treatment with Biochar

Stormwater **BIOCHAR** LLC

MAIL

6628 SE 68th Ave, Portland OR 97206

PHONE

503-789-6760

EMAIL

info@**Stormwater**.COM
BIOCHAR.COM

Stormwater **BIOCHAR**.COM
Biochar for stormwater treatment since 2010

THE RIGHT **BIOCHAR**,
THE RIGHT **BLEND**, DIALED IN.™

Pure Rain™ STORMWATER TREATMENT FILTRATION SYSTEMS

CUSTOM TANK



Stormwater BIOCHAR.COM

STORMWATER TREATMENT

Case Study 2021

Quarter	Date	Turbidity (NTU)	Zinc (ug/L)	Copper (ug/L)	NWTPH - Dx (mg/L)	pH (SU)	Oil Sheen
		25	117	14	10	5.0 - 9.0	Yes/No
Q2	04/25/17	5.2	1140	5.07		5.94	No
Q3	09/18/17	48.8	395	31.4		5.63	No
Q3	09/18/17	22.0	--	--	--	6.56	--
Q3	09/18/17 AVG	35.4	--	--	--	--	--
Q3	09/20/17	15.8	--	--	--	--	--
Q3	AVERAGE	25.6	--	--	--	--	--
Q4	10/12/17	6.0	289	6.17	0.27	5.88	No
Q4	10/12/17	5.1	--	--	--	--	--
Q4	10/12/17 AVG	5.5	--	--	--	--	--
Q1	02/28/18	11.53	608	12	0.14	7.28	No
Q1	02/28/18	9.0	--	--	--	--	--
Q1	2/28/18 AVG	10.27	--	--	--	--	--
Q2	06/09/18	4.6	149	11.9	0.489	7.03	No
Q4	10/05/18	7.9	312	34.7	1.19	7.93	No
Q1	02/11/19	10.3	524	6.36	0.0982	7.27	No
Q2	04/05/19	22.7	561	9.68	0.139	7.78	No
Q3	09/09/19	7.7	193	9.54	0.189	7.51	No
Q4	11/18/19	8.63	431	18.6	0.351	7.25	No
Q1	01/23/20	74.57	694	27.4	0.277	7.31	No
Q1	02/05/20	23.6	--	--	--	--	--
Q1	03/06/20	8.32	--	--	--	--	--
Q1	AVERAGE	35.50	--	--	--	--	--
Q2	05/12/20	15.8	645	27.4	1.14	7.52	No
Q3	09/23/20	14.5	276	8.83	0.33	7.43	No
Q4	10/13/20	6.1	477	9.25	0.15	7.87	No
Q1	01/12/21	12.8	29.6	<2.0	CA	CA	No

“We wanted to share some good news following sampling this month! (Q1 2021) The analytical results were under all the benchmarks for the first time and non-detect for copper!”

First Quarter Test after Treatment tank Installed.

Second Quarter Test Results - Pre & Post Treatment

Date of Test	Parameter Tested	% Change	PRE Treatment	Unit of Measure	POST Treatment	Unit of Measure	Amount of Media	Size Screen	Other info about site
5/25/21	Turbidity	59.7%	14.5	NTU	5.84	NTU	25 CY	33"	12' x 22' Box
5/25/21	pH	0%	8.14	SU	8.15	SU	25 CY	33"	12' x 22' Box
5/25/21	Copper	71.4%	16.2	ug/L	4.63	ug/L	25 CY	33"	12' x 22' Box
5/25/21	Zinc	94.5%	744	ug/L	40.6	ug/L	25 CY	33"	12' x 22' Box



Stormwater BIOCHAR.COM

Biochar for stormwater treatment since 2010

THE RIGHT **BIOCHAR**,
THE RIGHT **BLEND**, DIALED IN.™